


NOTE:

and authorized by local postal officials. unit is for private delivery only unless approved specification requirements as shown below. This This unit does not meet the USPS installation

- 17½′ ACTUAL —







USPS STD-4C Installation requirements include:

- 1. No parcel locker may be positioned lower than 15" (interior bottom shelf) from the finished floor.
- ы finished floor. At least one patron compartment shall be positioned less than 48" from the
- shelf) from the finished floor. No patron lock shall be positioned higher than 67" from the finished floor. No patron compartment shall be positioned lower than 28" (interior bottom
- The USPS Arrow Lock shall be positioned 36" to 48" above the finished floor.

Postal Products Unlimited, Inc. Milwaukee, WI 53207-2649 www postalproducts com 500 W. Oklahoma Ave (800) 229-4500

Product: 4C Horizontal - F Series "FRANKFORT"

Model: N1029418

Date: 12/14/10 Scale: NTS Drawn By: JER Checked By: Ħ